

testimonial

"Klick were happy to make several revisions to the design until we were happy. I was impressed with the quality of work and Klick's ability to make changes to the layout to accommodate site conditions without any fuss or delay to the project. We are delighted with our new art rooms which have plenty of storage space, feel light and spacious and are extremely functional."

Peter Jenkins – Deputy Head, Kennet School, Thatcham, Berkshire

Art room refurbishment for **Kennet School, Thatcham, Berkshire**

Installation of furniture and full refurbishment for 2 Art rooms and store room

Value: £68k

Duration of works: 4 weeks

Project Details:-

- > Free comprehensive design and consultation service
- > 2D and 3D CAD drawings provided, illustrating layouts
- > Full project management service
- > Remove tiles and install hygienic splashback
- > Removal of existing furniture and redundant services
- > Removal of existing archway and installation of doorway
- > Installation of new archway into the store room
- > Complete upgrade of electrical and mechanical services
- > Provision of IT benching & IT services
- > Supply and installation of furniture
- > Decoration and flooring renewed
- > Final connections, commissioning and certification of all works

Klick Technology completed a full refurbishment of 2 art rooms, improving access into the store room and creating space for a textiles area. The school selected 25mm Velstone for the worktop material throughout. Large tables and shelving were also supplied in Velstone which is very robust and ideally suited for use in an art room.

The specification of the A1 plan chests was critical as the school had experienced problems with previous models from other suppliers. Klick submitted a sample of our design which features 'Accuride' telescopic drawer runners with a ball bearing action. This was preferred and selected by the school.

Vulcathene clay traps were fitted in the cupboards under the sinks, which enables easy removal of clay to avoid blockages.

Site conditions meant that some minor alterations had to be made, but with no delay to the schedule.

A1 Plan chest drawers



Velstone tables



Large sink with clay trap



Perimeter benching

